



CITY OF ROCKY FORD INVITATION FOR BIDS

Asphalt Utility Cut Restoration Services
Bid Due Date: July 30, 2026, at 2:00 p.m.

BID NOTICE

The City of Rocky Ford is accepting sealed bids from qualified contractors to provide asphalt utility cut restoration services on an as-needed basis.

The successful contractor shall furnish all labor, materials, equipment, traffic control, hauling, disposal, compaction, cleanup, and incidentals necessary to restore asphalt pavement following City utility repairs.

This contract is intended to establish unit prices for various sizes of utility cuts. Quantities are estimates only, and the city does not guarantee any minimum amount of work.

The City reserves the right to accept or reject any or all bids, waive informalities, and award the contract in the best interest of the City.

CONTRACTOR INFORMATION

Company: _____

Contact Person: _____

Address: _____

City/State/Zip: _____

Phone: _____

Email: _____

Federal Tax ID: _____

Authorized Signature: _____

Date: _____

SCOPE OF WORK

The contractor shall:

- Coordinate work with the City of Rocky Ford's Public Works Director.
- Provide all required traffic control.
- Saw cut pavement to neat, straight lines.
- Remove existing asphalt and unsuitable material.
- Compact the subgrade and aggregate base.
- Place and compact hot mix asphalt to match existing grade.
- Restore disturbed areas.
- Remove all debris and leave the site clean.
- Meet all applicable City standards.

TECHNICAL SPECIFICATIONS

Asphalt Utility Cut Restoration

1. GENERAL

These specifications establish the minimum requirements for restoring asphalt pavement following utility repairs performed within City streets, alleys, and rights-of-way. The contractor shall furnish all labor, equipment, materials, traffic control, supervision, and incidentals necessary to complete each restoration.

2. APPLICABLE STANDARDS

Work shall conform to the latest applicable standards of:

- Colorado Department of Transportation (CDOT) Standard Specifications
- Manual on Uniform Traffic Control Devices (MUTCD)
- OSHA Safety Regulations
- City of Rocky Ford Standards

3. TRAFFIC CONTROL

- The contractor shall provide all traffic control necessary to safely complete the work.
- Traffic control shall comply with the current MUTCD.
- Access shall be maintained for emergency vehicles whenever practical.

4. SAW CUTTING

- Existing pavement shall be saw cut into neat, straight lines.
- Broken or jagged edges will not be accepted.
- The Public Works Director may require larger saw cuts if pavement damage extends beyond the excavation.

5. EXCAVATION PREPARATION

- Loose or unsuitable material shall be removed.
- The subgrade shall be compacted prior to placement of base material.
- Additional excavation required because of unsuitable material shall be approved by the City before payment.

6. AGGREGATE BASE

- Where base material has been disturbed, the contractor shall replace it with approved Class 6 road base.
- Base shall be placed in lifts not exceeding 6 inches.
- Each lift shall be mechanically compacted.

7. ASPHALT

- Hot Mix Asphalt shall meet current CDOT specifications.
- Minimum compacted thickness shall be:
- Match existing pavement thickness, or
- Three (3) inches minimum, whichever is greater.
- Multiple lifts may be required.

8. TACK COAT

A tack coat shall be applied to all vertical pavement edges immediately before asphalt placement.

9. COMPACTION

- Asphalt shall be compacted using approved rollers or vibratory compactors.
- The finished repair shall be dense, smooth, and free from segregation or roller marks.

10. FINISHED SURFACE

Completed repairs shall:

- Match the surrounding roadway.
- Be flush with existing pavement.
- Not vary more than 1/4 inch above or below the adjacent pavement.
- Drain properly.
- Be free of depressions or birdbaths.

11. CLEANUP

- Upon completion of work, the contractor shall:
- Remove excess asphalt.
- Remove debris.
- Sweep the roadway.
- Restore disturbed shoulders.
- Reopen the roadway to traffic.

12. WARRANTY

The contractor shall warrant all work for one (1) year from the date of acceptance.

During the warranty period, the contractor shall repair, at no cost to the City, any defects including but not limited to:

- Settlement
- Rutting
- Raveling
- Edge failure
- Separation
- Improper compaction
- Surface cracking related to workmanship
- Repairs shall be completed within thirty (30) calendar days of written notification unless otherwise approved by the Public Works Director.

13. PAYMENT

No additional compensation shall be allowed unless authorized in writing by the Public Works Director.

14. INSPECTION

The City reserves the right to inspect any work in progress. Work failing to meet these specifications shall be removed and replaced at the contractor's expense.

15. ACCEPTANCE

Final acceptance shall be made by the Public Works Director after inspection and verification that all work conforms to these specifications. Acceptance does not relieve the contractor of warranty obligations.

16. PROJECT LOCATIONS AND APPROXIMATE REPAIR AREA (contractor responsible for their own in-field measurements)

1. **1509 Pine Street** Approximate Dimensions: 13' x 16' Approximate Area: 208 Square Feet
2. **1503 Pine Street** Approximate Dimensions: 11' x 18' Approximate Area: 198 Square Feet
3. **7th Street and Pine Street** Approximate Dimensions: 9' x 18' Approximate Area: 162 Square Feet
4. **Sycamore Street between 7th Street and 8th Street** Approximate Dimensions: 10' x 16' Approximate Area: 160 Square Feet
5. **619 South 6th Street** Approximate Dimensions: 15' x 18' Approximate Area: 270 Square Feet
6. **511 South 2nd Street** Approximate Dimensions: 9' x 15' Approximate Area: 135 Square Feet
7. **7th Street and Walnut Street** Approximate Dimensions: 5' x 16' Approximate Area: 80 Square Feet
8. **612 North 7th Street** Approximate Dimensions: 8' x 10' Approximate Area: 80 Square Feet
9. **Spruce Street and 8th Street** Approximate Dimensions: 20' x 5' Approximate Area: 100 Square Feet
10. **402 Willow Avenue** Approximate Dimensions: 15' x 9' Approximate Area: 135 Square Feet
11. **Willow Avenue and Main Street** Approximate Dimensions: 23' x 7' Approximate Area: 161 Square Feet
12. **620 Willow Avenue** Approximate Dimensions: 23' x 58' Approximate Area: 1,334 Square Feet
13. **Chestnut Avenue between 3rd Street and 4th Street** Approximate Dimensions: 16' x 20' Approximate Area: 320 Square Feet
14. **93 Yucca Avenue** Approximate Dimensions: 15' x 20' Approximate Area: 300 Square Feet
15. **407 South 8th Street** Approximate Dimensions: 35' x 6' Approximate Area: 210 Square Feet
16. **401 South 14th Street** Approximate Dimensions: 17' x 6' Approximate Area: 102 Square Feet
17. **407 South 13th Street** Approximate Dimensions: 8' x 7' Approximate Area: 56 Square Feet
18. **Locust between 14th Street and 15th Street** Approximate Dimensions: 26' x 9' Approximate Area: 234 Square Feet
19. **Swink Avenue and Elm Avenue at 10th Street** Approximate Dimensions: 29' x 9' Approximate Area: 261 Square Feet
20. **711 North 13th Street** Approximate Dimensions: 22' x 11' Approximate Area: 242 Square Feet
21. **506 North 13th Street** Approximate Dimensions: 13' x 12' Approximate Area: 156 Square Feet

TOTAL APPROXIMATE REPAIR AREA: 5,124 Square Feet

Contractors shall include all labor, materials, equipment, traffic control, saw cutting, removal, disposal, compaction, asphalt placement, cleanup, and all incidentals necessary to complete the project in accordance with City specifications.

RESPONSE REQUIREMENTS

Unless otherwise approved by the Public Works Director:
Scheduled repairs shall be completed within 30 calendar days after notification.

REFERENCES

Please provide three references:

Agency: _____

Contact: _____

Phone: _____

Agency: _____

Contact: _____

Phone: _____

Agency: _____

Contact: _____

Phone: _____

For more information or questions, please contact Rick Long, Public Works Director, at 719-254-7414, Ext 105 or rlong@rockyford-co.gov.

REQUIRED SUBMITTALS CHECKLIST

The following documents shall accompany the bid:

- Completed Bid Forms
- Certificate of Insurance
- W-9
- Contractor License Information (if applicable)
- Three References
- List of Available Equipment
- Estimated Response Time

AWARD

The City intends to award this contract to the responsive and responsible bidder whose proposal is determined to be in the best interest of the City of Rocky Ford. The City reserves the right to consider price, qualifications, experience, availability, references, response time, and overall value.

CITY USE ONLY – DO NOT WRITE BELOW

Date Received: _____ Time Received: _____

Received By: _____ Award Recommendation: _____

Approved By: _____ Comments: _____

CITY OF ROCKY FORD

ASPHALT UTILITY CUT BID SHEET (PER LOCATION)

Bid Submission Form – All in Unit Price by Location

INSTRUCTIONS:

Enter a **unit price for each individual utility cut location listed below.**

Each location shall include full restoration in accordance with City specifications.

Pricing shall include all labor, materials, equipment, traffic control, base repair, asphalt, compaction, cleanup, and incidentals.

LOCATION NUMBER	ADDRESS	CUT SIZE	TOTAL SQ FT	BID TOTAL
1	1509 PINE			
2	1503 PINE			
3	7TH AND PINE			
4	SYCAMORE 7TH AND 8TH ST			
5	619 S 6TH ST			
6	511 S 2ND ST			
7	7TH ST AT WALNUT			
8	612 N 7TH ST			
9	SPRUCE AT 8TH ST			
10	402 WILLOW			
11	WILLOW AND MAIN ST			
12	620 WILLOW			
13	CHESTNUT BETWEEN 3RD AND 4TH			
14	93 YUCCA			
15	407 S 8TH ST			
16	401 S 14TH ST			
17	407 S 13 ST			
18	LOCUST BETWEEN 14TH AND 15TH			
19	SWINK/ELM AT 10TH ST			
20	711 N 13TH ST			
21	506 N 13TH ST			

CERTIFICATION

I hereby certify that the prices submitted are firm and valid for the duration of the contract period and that all work will be completed in accordance with City specifications.

Signature: _____

Title: _____ **Date:** _____